

Laboratory Test Report

1.75" Slit Film_Rubber_Sand_ShockDrain KBA 780

Job No.	100665/10840
Client Information	Flexground c/o SprintPlay 2140 E. Cedar Street Tempe, AZ 85281
Test Type	Performance Evaluation
Sample Arrival Date	6/20/2025
Test Date(s)	7/2/2025, 7/17/2025
Report Date	7/24/2025
Report Status	Final

Prepared by **Adam Kalil**
Laboratory Manager



Checked by **Jeffrey Gentile**
Co-Founder & CFO



Notes:

1. This report has been prepared by Firefly Sports Testing with all reasonable skill, care and diligence within the terms of the contract with the Client and within the limitations of the resources devoted to it.
2. This report is confidential to the Client and Firefly Sports Testing accepts no responsibility whatsoever to third parties to whom this report, or any part thereof, is made known. Any such party relies upon the report at their own risk.
3. This report shall not be used for engineering or contractual purposes unless signed by the Author and the Checker and unless the report status is "Final."



LABORATORY TESTING PERFORMANCE EVALUATION



Summary

Firefly Sports Testing was commissioned to perform laboratory testing per the standards listed below.

Test Type	Test Method	Test Description
Wheelchair Accessibility	ASTM F1951-21	Standard Specification for Determination of Accessibility of Surface Systems Under and Around Playground Equipment

Table of Contents

Summary	2
General Information.....	2
Laboratory Conditions.....	2
Sample Description	2
Results Summary.....	2
ASTM F1951 Wheelchair Accessibility.....	3
Statement of Specificity	3
7.1 Degree Control	3
1.75" Slit Film_Rubber_Sand_ShockDrain KBA 780 Results.....	4
Example Results Graph	4
End of Report	4

General Information

Laboratory Conditions

Air Temperature (°F)	73, 71	Surface Temperature (°F)	72, 72
Humidity (%)	57, 52	Technician	AK, AC

Sample Description

Sample Name	1.75" Slit Film_Rubber_Sand_ShockDrain KBA 780		
Performance Infill	3 lb/ft ² Rubber	Synthetic Turf Product	1.75" Slit Film
Stabilizing Infill	3 lb/ft ² Sand	Shock Pad	En-Plast ShockDrain KBA 780
Infill Depth (mm)	35	Sub-Base	Concrete

Results Summary

System	Average Straight Propulsion Work/Ft	Average Work Ratio Straight Propulsion	Average Turning Propulsion Work/Ft	Average Work Ratio Turning Propulsion
7.1% Control	8.08	--	11.69	--
1.75" Slit Film_Rubber_Sand_ShockDrain KBA 780	3.37	0.42	6.38	0.55

Note: Per ASTM F1951-21, an Average Work Ratio <1 is considered passing



Unit D5 • 78 Londonderry Tpk • Hooksett • New Hampshire • 03106
Telephone: (603) 715-5453 • E-Mail: contact@fireflysportstesting.com



ASTM F1951 Wheelchair Accessibility

Wheelchair Make	Tracer SX5	Wheelchair Weight (lbs)	48
Wheelchair Model	TRSX5RC8P	Wheelchair Rider Weight (lbs)	170
Wheelchair Serial Number	14BM014949	Weight Distribution	40% - 60% Front-to-Rear

Statement of Specificity

The results reported herein reflect the performance of the described samples at the time of testing. The results are specific to the described samples. Samples of surfacing materials that do not closely match the described samples will perform differently.

7.1 Degree Control

7.1% Grade Baseline Straight Propulsion					
Parameter	Trial 1	Trial 2	Trial 3	Trial 4	Trial 5
Time (s)	8.0	8.0	8.0	8.0	8.0
Distance (in)	76.0	78.0	78.0	78.3	78.7
Distance (ft)	6.33	6.50	6.50	6.53	6.56
Total Work (ft lbs)	51.00	54.20	50.60	52.80	53.20
Work/ft (lbs)	8.05	8.34	7.79	8.09	8.11
Average Work/ft (lbs) (n=3)	8.08				

7.1% Grade Baseline Turning Propulsion					
Parameter	Trial 1	Trial 2	Trial 3	Trial 4	Trial 5
Time (s)	8	8	8	8	8
Angle Traveled (degrees)	90	90	90	90	91
Total Work (ft lbs)	39.20	33.40	37.60	40.00	33.40
Work/ft (lbs)	12.48	10.63	11.97	12.73	10.51
Average Work/ft (lbs)	11.69				

LABORATORY TESTING PERFORMANCE EVALUATION




1.75" Slit Film_Rubber_Sand_ShockDrain KBA 780 Results

1.75" Slit Film_Rubber_Sand_ShockDrain KBA 780 Straight Propulsion					
Parameter	Trial 1	Trial 2	Trial 3	Trial 4	Trial 5
Time (s)	8	6.5	8	7	7
Distance (in)	81	82	80	83	83
Distance (ft)	6.75	6.83	6.67	6.92	6.92
Total Work (ft lbs)	22.80	21.80	22.20	24.00	23.60
Work/ft (lbs)	3.38	3.19	3.33	3.47	3.41
Average Work/ft (lbs) (n=3)	3.37				

1.75" Slit Film_Rubber_Sand_ShockDrain KBA 780 Turning Propulsion					
Parameter	Trial 1	Trial 2	Trial 3	Trial 4	Trial 5
Time (s)	7.9	7.3	7.6	7.1	7
Angle Traveled (degrees)	90	90	93	96	91
Total Work (ft lbs)	23.60	22.00	21.80	18.20	14.40
Work/ft (lbs)	7.51	7.00	6.72	5.43	4.53
Average Work/ft (lbs)	6.38				

Example Results Graph



End of Report



Unit D5 • 78 Londonderry Tpk • Hooksett • New Hampshire • 03106
Telephone: (603) 715-5453 • E-Mail: contact@fireflysportstesting.com

